CONTRACT: BOLINWOOD SEWER SYSTEM IMPROVEMENTS

PROJECT: CIP #276-45

DATE: January 10, 2022

DOCUMENT 00 91 13

ADDENDA

ADDENDUM NUMBER [1]

DATE: JANUARY 10, 2022


PROJECT: BOLINWOOD SEWER SYSTEM IMPROVEMENTS

OWASA CIP NUMBER: 276-45

OWNER: ORANGE WATER AND SEWER AUTHORITY

ENGINEER: K. F. CARTER ENGINEERING COMPANY, PLLC

TO: ALL BIDDERS



KEVIN F. CARTER, P.E.

Digitally signed by KEVIN F. CARTER, P.E.
Date: 2022.01.10 13:59:56 -05'00'

This Addendum forms a part of the Contract Documents and modifies the Bidding Documents dated December 2021, Addendum Number 1 issued 01/10/2022, with amendments and additions/deletions noted herein below.

Acknowledge receipt of this Addendum in the space provided in the Bid Form. Failure to do so may disqualify the Bidder.

This Addendum consists of **3** pages, including the cover page.

CHANGES TO THE SPECIFICATIONS:

1. SECTION 02604 – UTILITY STRUCTURES

   - Page 02604-10, Subsection 3.06 (C) change the last line to read: "…shall be Duramer 1030 as manufactured by SewerKote, or the Dura-Plate/Sherflex (2300 Epoxy Cementitious Resurfacer, Dura-Plate 235 Multipurpose Epoxy Primer, Sherflex Elastomeric Polyurethane System as manufactured by Sherwin-Williams, or equal."

2. SECTION 09900 – PAINTING

   - Page 09900-14, Table 9-2, add the following to REF. 155 – PRODUCT: "Dura-Plate/Sherflex (2300 Epoxy Cementitious Resurfacer, Dura-Plate 235 Multipurpose Epoxy Primer, Sherflex Elastomeric Polyurethane System as manufactured by Sherwin-Williams".

CONTRACT: BOLINWOOD SEWER SYSTEM IMPROVEMENTS

PROJECT: CIP #276-45

DATE: January 10, 2022

CHANGES TO THE DRAWINGS:

1. DRAWING 11 of 12, update the MANHOLE SCHEDULE with **ATTACHMENT 1**. Note: Changes are highlighted in **red.**

END OF DOCUMENT

ATTACHMENT 1

MANHOLE SCHEDULE															
MANHOLE NUMBER	NORTHING	EASTING	DIAMETER (FT)	EXTENDED BASE (MIN)	TYPE OF MANHOLE	TYPE OF COVER	FRAMING OPENING (MIN)	VENT PIPE REQ'D	VENT PIPE ELEV	OUTSIDE STEPS REQ'D	CONCRETE BALLAST (CY)	INTERIOR LINING	EXPOSED EXTERIOR PAINTED	BOLTED JOINTS (#/JOINT)	HVED
1	790519.6459	1984301.5709	6	0.5'	DOG/DROP	WATERTIGHT	22½"	YES	332	NO	2	YES	YES	4	YES
2	790370.6965	1984198.4738	6	0.5'	STD/DROP	WATERTIGHT	22½"	NO		NO	-	YES	YES	-	NO
3	790236.3031	1984037.4977	6	0.5'	STD/DROP	WATERTIGHT	22½"	NO		NO	-	YES	YES	-	NO
4	790182.7779	1983825.2081	6	0.5'	STANDARD	WATERTIGHT	22½"	NO		NO	-	YES	YES	-	NO
5	790175.7317	1983797.3646	6	0.5'	STANDARD	WATERTIGHT	22½"	NO		NO	-	YES	YES	-	NO
6	790067.6070	1983715.5223	6	0.5'	STD/DROP	WATERTIGHT	22½"	NO		NO	2	YES	YES	4	YES
7	790013.2092	1983673.9552	6	0.5'	STANDARD	WATERTIGHT	22½"	YES	347	NO	2	YES	YES	4	NO
8	789857.8043	1983633.2683	6	0.5'	STANDARD	WATERTIGHT	22½"	NO		YES	2	YES	YES	4	NO
9	789681.8334	1983650.7372	6	0.5'	STANDARD	WATERTIGHT	22½"	NO		NO	2	YES	YES	4	NO
10	789667.0046	1983717.4714	6	0.5'	STANDARD	WATERTIGHT	22½"	NO		YES	2	YES	YES	4	YES
11	789589.6262	1983724.2080	6	0.5'	STD/DROP	WATERTIGHT	22½"	YES	355	YES	2	YES	YES	4	NO
6A	790090.4176	1983656.6645	6	0.5'	STD/DROP	WATERTIGHT	22½"	NO		NO	-	YES	YES	-	NO
7A	789935.7639	1983618.7556	6	0.5'	STANDARD	WATERTIGHT	22½"	NO		NO	2	YES	YES	4	NO
8A	789833.4918	1983713.6895	6	0.5'	STD/DROP	WATERTIGHT	22½"	YES	353	YES	2	YES	YES	4	NO
	HIGH VELOCITY ENERGY DISSIPATOR (HVED) REQUIRED (0554101)														