Orange Water and Sewer Authority

Our community's trusted partner for clean water and environmental protection

ADDENDA

ADDENDUM NUMBER 01

DATE: 4-24-2026

PROJECT: Honeysuckle Rd. Phase I Water Main Replacement Project (Material Only)

OWASA CIP No.: 275-20

OWNER: ORANGE WATER AND SEWER AUTHORITY

TO: ALL SUBMITTERS

This Addendum is to provide answers to questions submitted by suppliers concerning the material purchase for the upcoming Honeysuckle Rd. Phase I Water Main Replacement Project (Materials Only).

Addenda #01 consists of 1 page:

Questions:

1) Do the tapping saddles need to be double-strap or single-strap?

   A: All tapping saddles should be double strap saddles. Please refer to OWASA Manual of Standards, Specifications, and Design for further information.

2) What is to be included in the hydrant assembly?

   A: Just the 4' bury hydrant only.

3) Does the ultra-flex coupling need to be 7" long or 12" long?

   A: 12" long

4) Please provide more information on the fiberglass meter vault (size, mfg., traffic rating, etc.)

   A: After discussion the enclosure should be a large plastic meter box 15" x 27" x 18". Please refer to OWASA Manual of Standards, Specifications, and Design for further information.