Addendum #1

Cane Creek – Culvert Replacements

CIP #270-45

Date of Issue: 11/18/2026

Following are questions that have been submitted by potential bidders followed by responses in bold print.

1. Article 3 of the specifications mentions submitting with the bid contractor qualifications as described in Article 11. I am not seeing these requirements in Article 11. Please advise.
    a. **No qualifications are required with the bid. Please ignore the statement in Article 3.**
2. Do you have dimensions on the restorations of the road?
    a. **Per the scope of work given, the road restoration is assumed to be 18' wide and the length of the excavation needed to replace the culvert. The existing access road is a gravel road that has grown over with grass and weeds.**
3. Are y'all anticipating a trench repair over the pipe area into a mill and overlay on the surrounding road area? Or is the methods up to the contractor?
    a. **No mill and overlay is required as the existing road is gravel only, no asphalt pavement**.
4. Can you point me towards the details on how you'd like the trench and road repair done.
    a. **No detail has been provided. Notes on the trench and compaction are in the scopes of work**.
5. Will a storm water bypass pump be necessary? If so is there any flow data?
    a. **We are not anticipating a pump around. No flow data is available**.
6. Will rock/unsuitable soils/undercut all be contingencies with change orders? If not, is there a geotechnical report available?
    a. **No geotech report is available. If rock or undercut is encountered, it would be handled with a change order**.