

ADDENDA

ADDENDUM NO. 03

DATE: **November 5, 2021**

PROJECT: **EAST MAIN STREET SANITARY SEWER REHABILITATION AND REPLACEMENT – PHASE I**

OWASA CIP NUMBER: **276-63**

OWNER: **ORANGE WATER AND SEWER AUTHORITY**

ENGINEER: **McKim & Creed, Inc.**

TO: **Prospective Bidders**


This Addendum forms a part of the Contract Documents and modifies the Bidding Documents dated October 2021, with amendments and additions noted herein below.

Acknowledge receipt of this Addendum in the space provided in the Bid form. Failure to do so may disqualify the Bidder.

This Addendum consists of 1 page.

CHANGES TO THE DRAWINGS:

1. Add the following as notes to the NCDOT detail 654.01 issued in Addendum No. 2:
 - a. The backfill material shall be ABC stone. Excavated material shall be hauled off site and disposed of in accordance with State and Local regulations. ABC Stone backfill shall be compacted to a density of at least 95% of that obtained by compacting a sample of the material in accordance with AASHTO T-99 as modified by NCDOT. Compact top 12-inches of trench in 6-inch lifts to 100% Proctor, in accordance with the contract documents.
 - b. The pavement cut shall be defined by a straight edge preferably a machine saw cut.
 - c. For areas outside of NCDOT's East Main Street repaving project limits identified on sheet G3, mill and overlay is required. Mill existing asphalt and overlay with 1.5-inches of S9.5B. Mill and overlay limits will be reviewed in the field and subject to the provisions of the NCDOT encroachment agreement.
 - d. The asphalt pavement material shall be installed and compacted thoroughly to achieve a smooth level path.
 - e. All pavement shall be repaired within the same week it is cut.
 - f. Refer to NCDOT encroachment agreement special provisions for additional guidelines within NCDOT.



-END OF DOCUMENT-